






WATER VALVE, SURVEY MONUMENT, OR SEWER CLEAN OUT FRAME & GRADE ADJUSTMENT



LETTERS ON COVER TO BE AS FOLLOWS:
 "SEWER", "WATER", OR "SURVEY" AS DIRECTED
 TOTAL WIDTH OF WORD "SEWER" OR "WATER"
 3-3/4". TOTAL WIDTH OF WORD "SURVEY"
 4-1/2". LETTER SIZE 5/8" x 3/4", RAISED 1/16"
 ABOVE LEVEL OF COVER, TYPE OF LETTERS
 TO BE SUBMITTED FOR APPROVAL.






8" C.I. FRAME AND COVER

1) IN PAVED MAJOR ARTERIAL STREETS, CONCRETE COLLARS SHALL BE SCORED RADIALLY AT QUARTER-CIRCLE POINTS AND SCORES SHALL BE 1/4" WIDE BY 1/2" DEEP. CONCRETE SURFACE SHALL BE ROUGH BROOM FINISHED. NO TRAFFIC SHALL BE ALLOWED ON COLLARS UNTIL CONCRETE REACHES MINIMUM 2500 PSI ON ALL STREETS.

2) LETTERS ON COVER TO BE AS FOLLOWS: "SEWER", "WATER", OR "SURVEY" AS DIRECTED. TOTAL WIDTH OF WORD "SEWER" OR "WATER" 3-3/4". TOTAL WIDTH OF WORD "SURVEY" 4-1/2". LETTER SIZE 5/8" X 3/4", RAISED 1/16" ABOVE LEVEL OF COVER. TYPE OF LETTERS TO BE SUBMITTED FOR APPROVAL. CASTINGS TO CONFORM TO SECT. 787.

3) COMPACTION TO CONFORM TO SECT. 301 OR 601.



COVER SECTION A-A

